

SECTION 01112 DESCRIPTION OF WORK

PART ONE -- GENERAL

1.1 SUMMARY

A. The work to be done under this Contract includes the furnishing of project management, labor, materials, tools and equipment for the construction of the SANTA MONICA BOULEVARD TRANSIT PARKWAY for the City of Los Angeles, all in accordance with the Contract Documents, including the GENERAL CONDITIONS, GENERAL REQUIREMENTS, TECHNICAL SPECIFICATIONS and Contract Drawings.

B. SCOPE OF WORK

The work to be done consists of reconstructing and reconfiguring "Big" and "Little" Santa Monica Boulevards from the San Diego Freeway to the Beverly Hill City Limits. This project will transform the two existing roadways and the existing "unused" railroad right-of-way into a "Classic Boulevard". The general items of work on this project include the following:

1. Grading, paving and reconstruction of the abandoned railroad right-of-way through the entire project limits to develop the new combined Boulevard, intersections, medians and turn lane facilities;
2. Construction of new curb, gutter, sidewalks, islands, medians, and frontage roads on Santa Monica Boulevard;
3. Construction of three retaining walls: a wall near Malcolm Avenue on the south frontage road, a retaining wall north of Century Park West and a retaining wall along the south side of the Boulevard from Prosser Avenue to Pandora Avenue;
4. Construction of storm drain facilities throughout the entire project limits.
5. Installation of traffic striping and traffic signal control equipment throughout the entire length of the proposed project and Changeable Message Signs;
6. Installation of street lights, hardscape and public arts elements;
7. Widening of northbound and southbound I-405 Freeway on-ramps, including landscaping, at Santa Monica Boulevard and construction of a sound wall along the southbound on-ramp;
8. Rehabilitation of sewers within project limits;
9. Construction of DWP underground conduit and substructures from Fox Hills Drive to Moreno Drive.
10. Widening of Veteran Ave and Beverly Glen Boulevard;

11. Construction of concrete blanket to protect existing MWD water main.

1.2 GENERAL SCOPE OF WORK

- A. **Work In This Contract:** Work in this Contract includes all labor, materials and equipment necessary for construction of the SANTA MONICA BOULEVARD TRANSIT PARKWAY PROJECT as noted on the Contract Drawings and in the Contract Documents including the GENERAL CONDITIONS, GENERAL REQUIREMENTS and TECHNICAL SPECIFICATIONS.
- B. **Work Not In This Contract:** "Work not in this Contract," "Work by others" and "Work by others but arranged and paid for by CONTRACTOR" are listed as follows:
 1. All work, materials, or equipment indicated on the Contract Drawings or in the Contract Documents as "Not in Contract" or "N.I.C." or anything with implied exclusion from the Contract in any manner.
 2. All work or equipment indicated on the Contract Drawings or in the Contract Documents as "work by others," and "work by others, but arranged and paid for by CONTRACTOR." The CONTRACTOR shall provide all necessary coordination, arrangement, and scheduling in accordance with General Conditions, Contract Drawings, and other Sections of the Contract Documents. CONTRACTOR shall appropriately pay for all charges, fees and costs specified to be paid for by the CONTRACTOR.
- C. **Related Work:**
 1. Documents affecting work of this Contract include, but are not limited to, the GENERAL CONDITIONS, GENERAL REQUIREMENTS, TECHNICAL SPECIFICATIONS and other sections of the Contract Documents.
 2. The work of other Contracts is described in the various Contract Documents. Lists of these documents are in the possession of the CITY and where they are available for inspection by interested parties.

1.3 PROJECT IDENTIFICATION

- A. **General:**
 1. The Project Name is SANTA MONICA BOULEVARD TRANSIT PARKWAY.
 2. Contract Documents have been prepared by the CITY OF LOS ANGELES, BUREAU OF ENGINEERING.

1.4 SUPPLEMENTAL INFORMATION

The following supplemental information is part of the Contract Documents:

- A. Geotechnical Investigation for Santa Monica Transit Parkway Project – March 28, 2002

- B. Geotechnical Report for Interstate 405-Freeway, North and Southbound On Ramp at Santa Monica Boulevard – March 28, 2002
- C. Summary of First Utility Notice Replies

1.5 GROUND BREAKING CEREMONY

The CONTRACTOR shall provide the Ground Breaking Ceremony for this project. The ceremony may occur before the Notice-to-Proceed is issued. The CONTRACTOR shall include in the contract cost and verify with the ENGINEER the ceremony schedule after the award of the contract. The CONTRACTOR shall prepare, after the award of the contract, all submittals for the construction sign and secure all necessary approvals. The CONTRACTOR shall provide necessary coordination for the Ground Breaking Ceremony. The Ground Breaking Ceremony and any subsequent project ceremonies required by the ENGINEER shall be paid for under the Fixed Allowance Bid Item, "Construction Mitigation and Special Events.

PART TWO – PRODUCTS (NOT APPLICABLE)

PART THREE - EXECUTION

3.1 **ADMINISTRATION OF CONSTRUCTION**

All work of this Contract will be administered by the ENGINEER and INSPECTOR.

(END OF SECTION)